

LEGEND:

- SHAFT
- REINFORCED CONCRETE, C30/37
- REINFORCED CONCRETE, C30/37
- AXIS

MATERIALS:

- VERTICAL STRUCTURES: C30/37-XC1-D_{max}=22 mm-CI 0.4-S4
- HORIZONTAL STRUCTURES: C30/37-XC1-D_{max}=22 mm-CI 0.4-S4
- MONOLITHIC LANDING: C30/37-XC1-D_{max}=22 mm-CI 0.4-S4
- BALCONIES: C30/37-XC1, XF3-D_{max}=16 mm-CI 0.4-S4

STEEL: B500A

ISOKORB:

T TYPE K-M2-VI-REI120-CV35-X80-H250-6.0

STAIRCASE:


Monolithic staircase, 160/300 mm

DEFINITION:

- TS - TOP SLAB
 - BS - BOTTOM SLAB
 - hs - HEIGHT OF THE SLAB
- 1 ISI UNIT HALFEN HIT (impact sound insulation)
 - 2 TRAPEZ BOX HALFEN HBB-0 for in-situ cast concrete landing
 - 3 PERIMETER JOINT INSULATION HALFEN HTPL

DETAIL 1

SCALE 1:50



Czech Technical University In Prague		ČVUT	
FACULTY OF CIVIL ENGINEERING THAKUROVA 7, PRAHA 6 - DEJVICE 166 29 prague 6			
Worked out by : HAYTHEM CHERIF	Year:	2020/2021	
Task: Residential building	Date:	24/05/2020	
Purpose: Diploma Thesis	Scale:	1:100	
Drawing: Formwork drawing	Format:	A1	
	Drawing number:	4	